



CEDAR HOLLOW FIRE DEPARTMENT

Fire Prevention Bureau — Construction Plan Review Section

910 Ridgeway Ave, Cedar Hollow, AZ 85338 • (555) 388-4100 • fireprevention@cedarhollowaz.gov

PLAN REVIEW CORRECTION NOTICE

THIS IS NOT A PERMIT. DO NOT BEGIN WORK.

Permit No.	FA-2026-00731	Review No.	2 of 3 (Recheck)	Issued	08/06/2026
Project	Larkspur Senior Living — Fire Alarm & Sprinkler Deferred Submittal			Occupancy	I-2 / R-2 mixed
Address	2255 N. Larkspur Trail, Cedar Hollow, AZ 85338			Const. Type	V-A, Sprinklered
Applicant	Vantage Fire Systems, Inc. — attn: R. Delgado			Bldg Permit	B26-1140
Reviewer	Insp. Teresa Vaughn, CFPS t.vaughn@cedarhollowaz.gov (555) 388-4127			Codes	2021 IFC; NFPA 13, 72 (2022)

DISPOSITION: DENIED — CORRECTIONS REQUIRED. The submittal has been reviewed and does not comply. Correct the items listed below and resubmit through the ePermit portal. Respond to every item in writing, keyed to the item number, and cloud each change on the drawings. Items marked **CARRIED** were issued on Review No. 1 (dated 07/09/2026) and were not adequately addressed; a third review will incur a re-review fee of \$185.00 per hour, one hour minimum, per Fee Schedule Res. 2025-44.

SECTION A — AUTOMATIC SPRINKLER SYSTEM (NFPA 13)

Item	Sheet / Location	Correction Required	Code Reference	Status
A-1	FP-2.1 Level 2, Wing B	Hydraulic calculations submitted are for the Level 1 remote area only. Provide calculations for the hydraulically most demanding area on each floor, including the Level 2 corridor cluster. The calculation summary sheet references a flow test dated 03/2021 — flow test data older than 12 months is not accepted.	NFPA 13 (2022) 28.2.4.2; IFC 903.3.1.1	CARRIED
A-2	FP-2.1, FP-2.2	Sprinkler spacing in the resident rooms exceeds the listed maximum for the quick-response head specified in the device schedule (Item 4). Either reduce spacing to 12'-0" on center or substitute a head with a greater listed coverage and update the schedule accordingly.	NFPA 13 (2022) 10.2.7.2	NEW
A-3	FP-1.0 Riser detail	The riser detail does not show a floor control assembly with control valve, waterflow switch, and test/drain for each floor. Multistory buildings require floor control valves. Revise the riser diagram.	NFPA 13 (2022) 16.9.5; CHFD Std. 4-02	NEW
A-4	FP-3.0	Attic space above Wing C is shown as unsprinklered and is described on the plans as "non-combustible concealed space." Field observation on 07/31/2026 found wood truss construction in this area. Provide sprinkler protection or submit documentation supporting the exception claimed.	NFPA 13 (2022) 9.2.1; IFC 903.3.1.1.1	NEW
A-5	General	Drawings are not sealed. All fire protection system drawings and calculations must bear the seal and signature of a NICET Level III (or higher) technician or an Arizona registered professional engineer.	A.R.S. §32-144; CHFD Admin. Policy 12	CARRIED

SECTION B — FIRE ALARM & DETECTION (NFPA 72)

Item	Sheet / Location	Correction Required	Code Reference	Status
B-1	FA-1.1	Battery calculations show 22.1 hours standby. Required standby is 24 hours plus 15 minutes of alarm at full load. Recalculate and resize batteries; include the derating factor for end-of-life.	NFPA 72 (2022) 10.6.7.2.1	NEW

B-2	FA-1.2 Rooms 214–229	Notification appliance candela ratings are not indicated on the plan. Provide candela values at each device and a spacing/coverage calculation demonstrating compliance for sleeping areas (minimum 177 cd at pillow level where required).	NFPA 72 (2022) 18.5.5, 18.5.5.7	CARRIED
B-3	FA-2.0	Duct smoke detector locations are shown for AHU-1 and AHU-2 but not for AHU-3 (2,400 CFM). Provide detection or demonstrate the unit is below threshold.	IMC 606.2.1; NFPA 72 17.7.5	NEW
B-4	Narrative, p. 3	The sequence of operations matrix does not address elevator recall. Provide Phase I emergency recall operation for the designated and alternate levels, and include lobby smoke detector locations on FA-1.1.	NFPA 72 (2022) 21.3; ASME A17.1	NEW

SECTION C — SITE & ACCESS (INFORMATIONAL — NO RESPONSE REQUIRED)

Item	Sheet / Location	Note	Code Reference	Status
C-1	C-3.0	Fire department connection and hydrant locations were approved under the site plan review (SP-2025-0902) and are not re-reviewed here. Any field relocation requires prior approval from this office.	—	INFO
C-2	—	Knox box installation and keying must be scheduled with the Bureau at least 10 business days before the final inspection. This does not affect plan approval.	IFC 506.1	INFO

T. Vaughn

Teresa Vaughn, CFPS — Fire Protection Plans Examiner
Cedar Hollow Fire Department, Fire Prevention Bureau
t.vaughn@cedarhollowaz.gov | (555) 388-4127

Resubmittals are accepted electronically only. Include: (1) this correction notice, (2) a written response letter keyed to each item number, (3) revised drawings with clouded changes and a revision delta, and (4) revised calculations. Partial resubmittals will be rejected at intake. Plan review approval expires 180 days from the date of approval if a permit is not issued. Appeals of any determination in this notice may be filed with the Fire Code Board of Appeals within 30 calendar days per IFC 109.